## IV. Takeoffs, Landings, and Go-Arounds

Task	N. Go-Around/Rejected Landing
References	FAA-H-8083-3, FAA-H-8083-23; POH/AFM; AIM
Objective	To determine that the applicant exhibits satisfactory knowledge, risk management, and skills associated with a go-around/rejected landing with emphasis on factors that contribute to landing conditions that may require a go-around.
Knowledge	The applicant demonstrates understanding of:
PA.IV.N.K1	A stabilized approach, to include energy management concepts.
PA.IV.N.K2	Effects of atmospheric conditions, including wind and density altitude on a go-around or rejected landing.
PA.IV.N.K3	Wind correction techniques on takeoff/departure and approach/landing.
Risk Management	The applicant demonstrates the ability to identify, assess and mitigate risks, encompassing:
PA.IV.N.R1	Delayed recognition of the need for a go-around/rejected landing.
PA.IV.N.R2	Delayed performance of a go-around at low altitude.
PA.IV.N.R3	Improper application of power.
PA.IV.N.R4	Improper airplane configuration.
PA.IV.N.R5	Collision hazards, to include aircraft, terrain, obstacles, wires, vehicles, vessels, persons, and wildlife.
PA.IV.N.R6	Low altitude maneuvering including stall, spin, or CFIT.
PA.IV.N.R7	Distractions, loss of situational awareness, or improper task management.
Skills	The applicant demonstrates the ability to:
PA.IV.N.S1	Complete the appropriate checklist.
PA.IV.N.S2	Make radio calls as appropriate.
PA.IV.N.S3	Make a timely decision to discontinue the approach to landing.
PA.IV.N.S4	Apply takeoff power immediately and transition to climb pitch attitude for $V_X$ or $V_Y$ as appropriate +10/-5 knots.
PA.IV.N.S5	Configure the airplane after a positive rate of climb has been verified or in accordance with airplane manufacturer's instructions.
PA.IV.N.S6	Maneuver to the side of the runway/landing area when necessary to clear and avoid conflicting traffic.
PA.IV.N.S7	Maintain V <sub>Y</sub> +10/-5 knots to a safe maneuvering altitude.
PA.IV.N.S8	Maintain directional control and proper wind-drift correction throughout the climb.